## **SPECIFICATION OF GENERATOR SET**

SI			
no	Specification	Qty	Rate
1	30 KVA- Genset with engine (Meeting Emission & Noise Compliant CPCB-II) developing 40-45 Bhp, Water cooled coupled with 30KVA (24kW) 3 phase, 415 V, 1500 RPM alternator, Std. control panel, base frame, Fuel tank(capacity 60 -70 Ltr), Battery with leads Battery charger and other accessories with type approved integral Canopy as a complete set. Including First fill of lube oil and Engine Safeties-LLOP, HWT.	1 Set	

## **Conditions**

- 1. Payment conditions: 75 % payment will be released after completing installation and successful running of the generator in all aspects. 20 % payment will be released after two month successful running of the generator. Balance 5 % payment will be released on submission of performance guarantees.
- **2. Price:** Price inclusive of all charges towards taxes, duty, freight, transportation, handling charges etc applicable at the time of delivery including commissioning of Generator set at Kerala Agro Super Bazaar at Thrissur after installation work.
- **3. Period of completion:** should undertake testing and commissioning of the generator set within 21 days from the date of placement of work order.
- **4.** The installation work will be done separately.

**Managing Director**